

PORTLAND PUBLIC SCHOOLS – FACILITY ADA ASSESSMENT

Creston Annex School Head Start
 August 31, 2009

Site Accessibility

Parking	(2) accessible spaces on-site in north parking lot (this lot is associated with Creston Annex). Replace directional signage directions for Head Start program to indicate accessible entry door. Add additional directional signage to indicate the path up to Creston school. Long paved path from parking to main building (approximately 6 ft rise in 380 ft, 1.5%).
Exterior Ramp at Entry	Verify North main entry ramp for slope is flatter than 1:20. If 1:12 to 1:20, add double handrails each side. Or lengthen ramp to flatter than 1:20 (5%) so that handrails are not required.

Accessible Route & Features

Multi-Purpose Room 7	Provide room door with lever handle hardware.
Office	Provide room door with lever handle hardware.
Classroom doors	Provide all classrooms with lever handle hardware.

Plumbing Elements

Drinking Fountain	Verify that drinking fountain inside the Multi-Purpose room complies with children's reach range accessibility standards.
-------------------	---

Communication Elements

Classrooms	Any need for assisted listening devices in programs at this school? Or within SPED classrooms?
Signage	Provide accessible signage at accessible restrooms and common spaces. If signage is provided at classrooms, provide accessible signage.

Special Spaces, Built-in Elements & Recreational Facilities

n/a	
-----	--

