

# PORTLAND PUBLIC SCHOOLS – FACILITY ADA ASSESSMENT

Kenton (De La Salle HS, Leased)  
August 31, 2009

## Site Accessibility

Northeast Parking	New NE parking lot and building additions. Parking lot size will require(1) accessible stall and access aisle (up to 25 vehicles). Verify final accessible stalls and aisles and any required curb cuts and access to an accessible path.
Portables	Verify that there is an accessible ramp and stairs to access Classrooms P1 and P2, and modify to provide them if needed. Add a compliant ramp and stairs an entrance to Classroom P3 (approximately 24 lf of ramp.)
West Front Entry	Double stairs up to front door. No handrails. Provide exterior handrails at exterior entry stairs (approximately 40 lf of rail.) Provide directional signage to accessible north entry.
East Entries	Exit doors to play ground from auditorium and gymnasium have exterior stairs. Provide compliant handrails on these stairs (approximately 20 lf of rail).
South Entry	Add exterior handrails at steps up to door (approximately 8 lf of rail.) Provide an accessible ramp (approximately 12 lf of ramp.)

## Accessible Route & Features

North Entry	Entry is at grade and accessible from sidewalk to the basement level. Verify for compliant door hardware and threshold. Provide accessibility signage outside entrance.
West Front Entry	Verify entry pair door clearances and threshold, and door hardware for accessibility compliance. Stairs at interior. Replace interior stair handrails with compliant handrails with top and bottom extensions (approximately 34 lf of rail.)
South Entry	Add compliant handrails at interior stairs west to classrooms (approximately 14 lf of rail.)
Elevator A	Add an elevator to access the south portion of the basement, first and second floors, and from the exterior. Suggested location would be outside the south end of the main corridor. This location would access the exterior, the south basement, including the girls restroom and the first and second floors. It does not access the north basement classes or boys restroom.
Elevator B	Add an elevator to access the north portion of the basement and building. Suggested location would be at the northeast corner of the north interior court. This would access through Classrooms 7 & 17, and Room J in the basement (approximately 40lf of corridor remodel.)
Ramp / Lift	At the two steps between the Gym and the main building wing main floor level, provide a ramp or lift (or integrate into elevator B solution.)
Stage	Provide a lift to access the stage (and connect the Auditorium to the Gym along an accessible route.)
Handrails	Verify that accessible handrails are provided in at least one stair from basement to the second floor. If not currently provided, the northwest stair



	is recommended (approximately 144 lf of rail.)
Auditorium	Verify interior auditorium entry pair door clearances and door hardware for accessibility compliance.
Common Room Doors	Verify that lever or pull hardware is provided at common room doors, and provide if needed.
Classrooms	Provide lever handle hardware at all classroom entry doors.

Plumbing Elements

Basement Boys Restroom	Provide an accessible toilet stall, clearances, toilet, grab bars, lavatory and accessories within reach ranges. Verify or replace entry doors for compliant width and clearances.
Basement Girls Restroom	Provide an accessible toilet stall, clearances, toilet, grab bars, lavatory and accessories within reach ranges. Verify or replace entry doors for compliant width and clearances.
Adult Unisex Restroom	Provide an accessible toilet, clearances, grab bars, lavatory and accessories within reach ranges on the main level. Verify or replace entry doors for compliant width and clearances.
Drinking Fountains	Verify one compliant height drinking fountain on the main floor. Provide an accessible drinking fountain on the basement level. If a drinking fountain is provided on the second floor, provide an accessible drinking fountain.

Communication Elements

Auditorium 22	Provide assisted listening devices.
Classrooms	Any need for assisted listening devices to any classroom?
Signage	Provide accessible signage at new accessible restrooms and common spaces. If signage is provided at classrooms, provide accessible signage.

Special Spaces, Built-in Elements & Recreational Facilities

Office	Verify that an accessible area of counter is provided, and modify if needed.
Library	Verify that an accessible area of counter is provided, and modify if needed.
Serving line	Verify that the serving line is at an accessible height, and modify if needed.
Play Areas	There are (0) soft surfacing play areas at this school.

