



# TERWILLIGER ACCESSIBILITY SUMMARY



Terwilliger School  
6318 SW Corbett Avenue  
Portland, OR 97239

## SUMMARY

All common areas at Terwilliger are located on the ground floor. Priority should be given to stair handrails and accessible ramps or lifts. The handrails, ramps and door hardware and comprise the majority of the upgrade work. The major accessibility upgrades for Terwilliger are summarized on this sheet.

## ACCESSIBILITY UPGRADES TO MEET 2008 ADA GUIDELINES

Site Elements	Accessible ramp at portable classrooms Accessible ramps at north entry Accessible handrails
Accessible Route & Reach Ranges	Accessible ramp or lift at north entry Accessible handrails Classroom lever handle hardware
Plumbing Elements	Accessible boys and girls restrooms Accessible staff unisex restroom Accessible dual-height drinking fountain Accessible sink
Communication Elements	Assisted listening device at assembly room Accessible exterior and interior signage
Recreational Facilities	Accessible play area soft surfacing & structure

## COST BREAKDOWN

Cost information provided is based on 2009 estimated unit costs for direct construction including general contractor overhead. Additionally, estimated hard costs and soft costs provided by PPS have been included.

Site Elements	\$106,077
Accessible Route & Reach Ranges	\$94,522
Plumbing Elements	\$33,484
Communication Elements	\$6,605
Special Spaces	\$0
Built-In Elements	\$0
Recreational Facilities	\$31,021
Special Education	\$0
Total	\$271,708